



Hook & Ladder Joint Reinforcement at 16" O.C. with Pintle Wire Tie & Washer

Air Space (1" Min. - 2" Max.)

Flashing System

Mortar Droppings Collection Device

Weep Hole Insert @ Max. 24" O.C.

Drip Edge

Owens Corning®  
FOAMULAR®  
250 XPS

CMU

Owens Corning® FOAMULAR®  
CW25 XPS

Termination Bar

NFPA 285 Compliant  
Air & Water Barrier

Waterproofing Through Wall  
Flashing

Below Grade Waterproofing  
Membrane

Drainboard

# Enclosure Solutions

## Concrete Masonry Unit Wall System

### Wall to Foundation Transition

Date: 05-03-16

Dwg. no. ES-CM-11

Vertical Section

NOTE: This drawing is a general reference intended to show common wall system assembly details. Actual details for each product will vary, therefore, details for each project must be reviewed and approved by the Architect of Record. Manufacturers assume no responsibility for final project drawings or field installation.